

Reconstruction of Mount Julian-Viamede & Reid's Road
Closing Date April 22, 2022

REVISED FOR OF TENDER – ADDENDUM#1

The Municipality reserves the right to cancel any or all items.

SECTION NO. 1 – Site Preparation, Removals, Erosion Control						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1.01	SP22	Insurance and Bonding	LS	1	\$ _____	\$ _____
1.02	SP23	Mobilization / Demobilization	LS	1	\$ _____	\$ _____
1.03	805 SP24	Straw Bale Check Dam	ea	10	\$ _____	\$ _____
1.04	805 SP24	Light Duty Silt Fence	m	315	\$ _____	\$ _____
1.05	805 SP24	Rock Check Dam	ea	5	\$ _____	\$ _____
1.06	510	Asphalt Removal	m ²	31,200	\$ _____	\$ _____
1.07	510	Culvert Removal	m	365	\$ _____	\$ _____
1.08	206	Ditching	m	9,600	\$ _____	\$ _____
1.09	510 SP25	Remove and Reinstall Mailbox	LS	1	\$ _____	\$ _____
1.10	510 SP25	Remove and Reinstall Road Sign	ea	30	\$ _____	\$ _____
1.11	206	Strip and Export Topsoil	m ²	31,500	\$ _____	\$ _____
1.12	180, 201 SP26	Tree Clearing and Grubbing	LS	1	\$ _____	\$ _____
1.13	180 206 SP27	Earth Excavation – Removed from site	m ³	17,000	\$ _____	\$ _____
1.14	706, SP 28	Traffic Control	LS	1	\$ _____	\$ _____

**Reconstruction of Mount Julian-Viamede & Reid's Road
Closing Date April 22, 2022**

SECTION NO. 1 – Site Preparation, Removals, Erosion Control						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1.15	314, 1010 SP 29	Import SSM	m ³	1,200	\$ _____	\$ _____
TOTAL SECTION NO. 1: (excluding HST)						\$ _____

SECTION NO. 2 – Drainage						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
2.01	401, 410, 421 SP30	375mm HDPE Driveway Culvert	m	195	\$ _____	\$ _____
2.02	401, 410, 421 SP30	450mm HDPE Driveway Culvert	m	110	\$ _____	\$ _____
2.03	401, 410, 421 SP30	450mm HDPE Cross Culvert c/w Frost Taper	m	155	\$ _____	\$ _____

**Reconstruction of Mount Julian-Viamede & Reid's Road
Closing Date April 22, 2022**

SECTION NO. 2 – Drainage						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
2.04	401, 410, 421 SP30	600mm HDPE Cross Culvert c/w Frost Taper	m	36	\$ _____	\$ _____
2.05	401, 410, 4211 SP30	750mm HDPE Cross Culvert c/w Frost Taper	m	20	\$ _____	\$ _____
2.06	401, 410, 4211 SP30	900mm HDPE Cross Culvert c/w Frost Taper	m	14	\$ _____	\$ _____
TOTAL SECTION NO. 2: (excluding HST)						\$ _____

SECTION NO. 3 – Road Construction						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
3.01	314, 1010, 501, SP 31	Granular 'B' Type I (250mm depth)	t	31,680	\$ _____	\$ _____
3.02	314, 1010, 501, SP 31	Granular 'A' (150mm depth) – Roadway	t	17,000	\$ _____	\$ _____
3.03	1010, 501, SP 31	Granular 'A' (150mm depth) - Driveway	t	600	\$ _____	\$ _____

**Reconstruction of Mount Julian-Viamede & Reid's Road
Closing Date April 22, 2022**

SECTION NO. 3 – Road Construction						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
3.04	802, 803, 804, SP 32	Hydro-seed and Topsoil	m ²	26,200	\$ _____	\$ _____
3.05	710, 1713 SP 33	Pavement Markings	LS	1	\$ _____	\$ _____
3.06	1010 501 SP 31	Granular 'A' – Shouldering/Rou nding	m ²	1,800	\$ _____	\$ _____
TOTAL SECTION NO. 3: (excluding HST)						\$ _____