



The Corporation of the Township of North Kawartha
Addendum # 1
Tender – RFT-02-22

**Reconstruction of Mount Julian-Viamede &
Reid's Road**

Date: April 19, 2022

This is to Acknowledge Receipt of Addendum

Company _____

Date Received _____

Authorized Signature _____

Position _____

**This form shall be included in all bid submissions and
acknowledged as per Page 43 of the Tender Document**

**The Corporation of the Township of North Kawartha reserves the right to accept or reject all
or part of any bid and also reserves the right to accept other than the lowest bid and to
cancel this call for bids at any time.**

This addendum shall form part of the tender document. Please note the following clarifications:

#	Question	Response
1	There is a 600mm Ø culvert visible on Sheet 11 on the contract drawing. Are you able to provide further details on this culvert?	The Updated Contract Drawings and Form of Tender, provide clarification on this item.
2	Does Item 3.02 Granular A include shouldering/rounding?	A new item has been added to the Form of Tender for granular 'a' shouldering/rounding. A revised special provision is provided on the next page.
3	Sheet 20 of the drawings indicates some Heavy Duty Silt Fence, can you confirm this and if needed a pay item added?	The Updated Contract Drawings indicate Light-Duty Silt Fence. Bidders shall note that all other Erosion and Sediment Control that may required for this project shall be included in this item.
4	Drawings indicate a Cross Culvert at Station 2+790 but does not provide any sizing or length.	Updated Contract Drawings and Form of Tender have included this cross culvert
5	Please verify and confirm quantities for Culvert Removals and New Culverts	Updated Contract Drawings and Form of Tender have included removals and new culverts
6	Please confirm the Granular A Driveway Quantity	Form of Tender has been updated to display the revised quantity
7	Please confirm the Hydroseed and Topsoil quantities	Form of Tender has been updated to display the revised quantity
8	Please confirm the Ditching quantities	Form of Tender has been updated to display the revised quantity
9	Driveway Culvert @ STA 1+410, indicates existing headwalls. How are we to be paid for removal and if required, their replacement?	Bidders shall include the cost of removal and restoration in their bid. Bidders shall note that on a project basis, that includes but is not limited to Rip-Rap, Headwalls, geo-textile etc. as indicated on the contract drawings.

10	Please provide a detail and section for the work required on Fire Routes 5,6, & 7	The Contract drawings provide adequate information for these areas.
11	Do the culverts crossing Fire Routes 5, 6 and 7 require a Frost Taper?	Yes, Bidders shall include a frost tape with these culvert installations. The Revised Form of Tender includes these items.
12	Is a step-joint required at the Connection to Hwy#28 and Northey's Bay Road.	Contract Drawing has been revised to indicate the step joint. Bidders shall note that any permits required shall be applied for and paid by the Successful Contractor
13	Could Strip and Reuse Topsoil be converted to m ² rather than m ³ . Also, please specify the depth of existing topsoil in the ditch line	Form of Tender has been revised to provide a square metre area for this item. Item has been revised to <u>Strip and Export Topsoil</u> Bidders shall note that approximately 30cm of topsoil is found throughout the project
14	It appears mailboxes are no longer within the contract limits, can you confirm?	Correct, the Form of Tender has been revised to remove this item.
15	Could X-Sections be supplied to provide more clarity on the cut-to-fill for this project?	Yes, cross sections for cut-to-fill have been provided in the Contract Drawings.
16	Can you please confirm the type of paint for traffic markings?	Water Borne as per OPS 1716

Additional Changes

- **Bidders shall read and replace SP 31 with the following:**

SP 31 Granular Materials – Item 3.01 to 3.03 & 3.06

OPSS 314 applies with the following amendments.

The scope of work under these items includes placement of granular material as outlined below:

- Compacted Granular “A” and “B” for road base construction
- Compacted Granular “A” for entrance construction
- Compacted Granular “A” for shouldering/rounding

Prior to delivery on-site, the material shall be tested at the source. The Contractor must provide the Municipality with test results indicating that the material to be supplied conforms to OPSS MUNI 1010. The testing must be performed by a Certified Laboratory. Compaction of granulars shall be in accordance with OPSS 501. The Contractor shall undertake quality control testing for compaction as per OPSS 501. The minimum frequency of compaction testing shall be one (1) test per 150 m for each lift of material. Written proof of the compaction (test results) shall be provided to the Contract Administrator prior to subsequent lifts of material being placed.

Payment for Items 3.01 to 3.03 will be by the tonne and based on weight tickets provided by the Contractor.

Payment for Item 3.06 will be by the square metre based on the contract documents.

- **Bidders shall remove and replace Pages 36 to 39 with the revised Form of Tender “Attachment #1, Revised Form of Tender”**
- **Bidders shall use the Updated and Revised Contract Drawings for bidding of the project. “Attachment #2, Revised Contract Drawings_X-Sections”**
- **The **Tender Closing Date** has been modified to:**

Date: Friday, April 22, 2022

Time: 2:00:00 p.m. (14:00:00) local time